

G:\KinderMorgan\339501_NEDProject\Work\Drafting\Standard_Details\E&S_Details\NH\CAD\NH_ES_DETAILS_001.dwg - PLOT TIME: 11/13/2015 10:35 PM

TRACKING

"TRACKING" WITH MACHINERY UP AND DOWN THE SLOPE PROVIDES GROOVES THAT WILL CATCH SEED, RAINFALL AND REDUCE RUNOFF.

GROOVED OR SERRATED SLOPE

6" TO 15"
1" TO 3"
2 OR FLATTER 1

NOTE:
GROOVE BY CUTTING SERRATIONS ALONG THE CONTOUR. IRREGULARITIES IN THE SOIL SURFACE CATCH RAINWATER, SEED, MULCH AND FERTILIZER.

SURFACE ROUGHENING

NOT TO SCALE

FORM NO. SR
REV. NO. 1

ISOMETRIC VIEW

EXCAVATE FOR STORAGE
1.5" TO 2.0" STONE FILLED CENTER
APRON
EARTH FILL
UNDISTURBED AREA

PROFILE

1' MIN.
L = 6 x D.A.
1' MIN.
VARIABLE
1.5" TO 2.0" STONE FILLED CENTER
6' MIN.
WEIR CREST
1.5" TO 2.0" STONE FILLED CENTER
2' APRON
FLOW
EXCAVATE FOR REQUIRED STORAGE

SECTION A-A

STONE OUTLET SEDIMENT TRAP

FORM NO. SOST
REV. NO. 2

ISOMETRIC VIEW

EXCAVATE, IF NECESSARY
PERFORATED RISER
OUTLET PROTECTION
EARTH EMBANKMENT

EMBANKMENT SECTION THROUGH BARREL & RISER

ALL SLOPES 3:1 OR FLATTER
6' MIN.
4' MAX.
PERFORATED RISER
ROCK OUTLET PROTECTION
ALL CONNECTIONS SHALL BE WATERTIGHT

PIPE OUTLET SEDIMENT TRAP

FORM NO. POST
REV. NO. 3

PLAN

EMERGENCY SPILLWAY (IN EXISTING GROUND)
TOP OF EMBANKMENT
SEDIMENT BASIN
RISER WITH TRASH RACK
BARREL
STABILIZED OUTLET

SECTION

TRASH RACK
CLEANOUT MARK
2' MIN.
SPILLWAY ELEV.
1' MIN.
EMERGENCY SPILLWAY (BEYOND)
EMBANKMENT STABILIZED WITH VEGETATION
FREEBOARD 1' MIN.
ENGINEERED SELECTED FILL PLACED IN LAYERS AND COMPACTED
SPILLWAY BARREL
STABILIZED OUTLET
DRAINAGE HOLES
ANTI-FLOTATION BLOCK
ANTI-SEEP COLLAR TYPICAL OF 2

NOTES:
1. THE TEMPORARY SEDIMENT BASIN, DESIGNED BY A QUALIFIED PROFESSIONAL, IS REQUIRED FOR DISTURBED AREAS GREATER THAN 5 ACRES WITHIN A DRAINAGE AREA LESS THAN 100 ACRES.
2. THE SEDIMENT BASIN WILL BE REMOVED WITHIN 3 YEARS.

TYPICAL SEDIMENT BASIN

FORM NO. TSB
REV. NO. 4

PLANVIEW

20' x 25' x 6" BLANKET
3/4" TO 1-1/2" STONE
SEDIMENT-LADEN WATER FROM PUMP
GEOTEXTILE DEWATERING BAG
FLOW
15'
10'
20'
10' ±
50' TO SILT FENCE OR BARRIER

PROFILE

PUMP DISCHARGE HOSE
4" MAX.
FLOW
6" THICK STONE BLANKET
EXTEND FABRIC 5' BEYOND STONE
PREPARED SUB-GRADE OR UNDISTURBED GROUND
GEOTEXTILE FABRIC UNDER STONE FOR EASE OF REMOVAL

NOTES:
1. GEOTEXTILE BAG MATERIAL BASED ON PARTICLE SIZE IN PUMPED WATER, I.E., FOR COARSE PARTICLES A WOVEN MATERIAL; FOR SILTS/CLAYS A NON-WOVEN MATERIAL.
2. DO NOT OVER PRESSURIZE BAG OR USE BEYOND CAPACITY.
3. LOCATE DISCHARGE SITE ON FLAT UPLAND AREAS AS FAR AWAY AS POSSIBLE FROM STREAMS, WETLANDS, OTHER RESOURCES AND POINTS OF CONCENTRATED FLOW.
4. DOWNGRADIENT FROM RECEIVING AREA MUST BE WELL VEGETATED OR OTHERWISE STABLE FROM EROSION, E.G., FOREST FLOOR OR COARSE GRAVEL/STONE.
5. DISCHARGE LOCATION SHALL MEET ALL REGULATORY SETBACKS FROM WETLANDS AND OTHER WATER COURSES.

GEOTEXTILE DEWATERING BAG

FORM NO. GDB
REV. NO. 5

ISOMETRIC VIEW

BLANKETS SHOULD BE INSTALLED VERTICALLY DOWNSLOPE.
TAMP SOIL OVER MAT/BLANKET
6' MIN.
2:1 SLOPE
MIN. 4" OVERLAP
12"
6"
1 1/2"
12"
STAPLES
BERM
4'
12"
NOT TO SCALE

TYPICAL SLOPE SOIL STABILIZATION

NOTES:
1. DIMENSIONS GIVEN IN THE DRAWINGS ARE EXAMPLES; DEVICE SHOULD BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
2. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.
3. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.
4. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.

EROSION BLANKETS SLOPE INSTALLATION

ADAPTED FROM J. MCCULLAH 1994

FORM NO. EBSI
REV. NO. 6

LONGITUDINAL ANCHOR TRENCH

TERMINAL SLOPE AND CHANNEL ANCHOR TRENCH

ISOMETRIC VIEW

STAKE AT 3'-5' INTERVALS.
CHANNEL BOTTOM
CHECK SLOT AT 25' INTERVALS

INITIAL CHANNEL ANCHOR TRENCH

INTERMITTENT CHECK SLOT

NOTES:
1. DIMENSIONS GIVEN IN THE DRAWINGS ARE EXAMPLES; DEVICE SHOULD BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
2. CHECK SLOTS TO BE CONSTRUCTED PER MANUFACTURER'S SPECIFICATIONS.
3. STAKING OR STAPLING LAYOUT PER MANUFACTURER'S SPECIFICATIONS.

EROSION BLANKETS CHANNEL INSTALLATION

FORM NO. EBCI
REV. NO. 7


NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

NORTHEAST ENERGY DIRECT PROJECT

NEW HAMPSHIRE


Section:	Township:	Range:
Co./Par.:	State: NEW HAMPSHIRE	
Division:	Op. Area:	
Drafter: BZ	Date:	Project ID:
Chk'd: DL	Date:	Scale:
Approved: CM	Date:	Filename:
Sheet: 1 of 13		Type:



TEMPORARY DIVERSION

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company


DRAWING NO. TD
 SHEET NO. 8



SLOPE DRAIN

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company


DRAWING NO. SD
 SHEET NO. 9



OVERSIDE DRAIN

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company


DRAWING NO. OD
 SHEET NO. 10



SILT FENCE INSTALLATION

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company


DRAWING NO. SF1
 SHEET NO. 11



SILT FENCE TYPICAL PLACEMENT-ONE SLOPE

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company


DRAWING NO. SF2
 SHEET NO. 12



SILT FENCE TYPICAL PLACEMENT-TWO SLOPES

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company

DRAWING NO. SF3
 SHEET NO. 13



SILT FENCE PLACEMENT FOR PERIMETER CONTROL

Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company

DRAWING NO. SF4
 SHEET NO. 14

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					


Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company

NORTHEAST ENERGY DIRECT PROJECT

NEW HAMPSHIRE

Section: _____ Township: _____ Range: _____
 Co./Par.: _____ State: NEW HAMPSHIRE
 Division: _____ Op. Area: _____
 Drafter: BZ Date: _____ Project ID: _____
 Chkd: DL Date: _____ Scale: _____
 Approved: CM Date: _____ Filename: _____

Sheet: 2 of 13
 Type: _____




NOTES:

1. THE BALES SHALL BE PLACED ON SLOPE CONTOUR.
2. BALES TO BE PLACED IN A ROW WITH THE ENDS TIGHTLY ABUTTING.
3. KEY IN BALES TO PREVENT EROSION OR FLOW UNDER BALES.
4. REFER TO DESCRIPTION OF "SILT FENCE" FOR DIAGRAMS ILLUSTRATING PLACEMENT OF BARRIERS FOR EFFECTIVE SEDIMENT CONTROL.

STRAW OR HAY BALE BARRIER


Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 SHBB 15



EROSION CONTROL MIX BERM TYPICAL PLACEMENT—ONE SLOPE

INSTALLATION WITH J-HOOKS OR "SMILES" INCREASES EROSION CONTROL MIX BERM EFFICIENCY.


Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 ECB1 16



EROSION CONTROL MIX BERM TYPICAL PLACEMENT—TWO SLOPES

INSTALLATION WITH J-HOOKS WILL INCREASE EROSION CONTROL MIX BERM EFFICIENCY AND REDUCE EROSION-CAUSING FAILURES.


Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 ECB2 17




EROSION CONTROL MIX BERM PLACEMENT FOR PERIMETER CONTROL

Discreet segments of compost berms, installed with J-hooks or 'smiles' will be much more effective.


Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 ECB3 18



Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 CCB 19




Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 SCD1 20



Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company
 CGSB 21


NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
NORTHEAST ENERGY DIRECT PROJECT NEW HAMPSHIRE					
Section:		Township:		Range:	
Co./Par.:		State:		NEW HAMPSHIRE	
Division:		Op. Area:			
Drafter: BZ		Date:		Project ID:	
Chk'd: DL		Date:		Scale:	
Approved: CM		Date:		Filename:	
				Sheet: 3 of 13	
				Type:	



**GRAVEL & WIRE MESH
DROP INLET
SEDIMENT BARRIER**

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

DRAWING NO. GW5B
DATE: 11/11/11
SCALE: 1\"/>




**TEMPORARY
GRAVEL
CONSTRUCTION
EXIT**

NOTES:
1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT.
2. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
3. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


DRAWING NO. TGCE
DATE: 11/11/11
SCALE: 1\"/>



**EXCAVATED
EARTH OUTLET
SEDIMENT TRAP**

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


DRAWING NO. EST1
DATE: 11/11/11
SCALE: 1\"/>



**EMBANKMENT
EARTH OUTLET
SEDIMENT TRAP**

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

DRAWING NO. EST2
DATE: 11/11/11
SCALE: 1\"/>



**CROSS SECTION
SCALE: N.T.S.**


**PLAN VIEW
SCALE: N.T.S.**

CONSTRUCTION PROCEDURE NOTES:
1. FLAG WETLAND BOUNDARIES AND INSTALL BOUNDARY SIGNS PRIOR TO CLEARING.
2. NO OVERNIGHT PARKING OR REFUELING OF MOBILE EQUIPMENT IS ALLOWED WITHIN 100 FEET OF WETLAND. PLACE "NO FUELING" SIGN POSTS 100 FEET BACK FROM WETLAND BOUNDARY. REFUEL STATIONARY EQUIPMENT AS PER SPCC PLAN.
3. INSTALL TEMPORARY SLOPE BREAKERS UPSLOPE OF WETLAND BOUNDARIES.
4. INSTALL PREFABRICATED EQUIPMENT MATS THROUGH ENTIRE WETLAND AREA ON THE WORKING SIDE OF THE CONSTRUCTION CORRIDOR.
5. AVOID ADJACENT WETLANDS. INSTALL SEDIMENT BARRIERS AT OUTER BOUNDARIES OF WETLAND AND ALONG BOTH WETLAND EDGES.
6. LIMIT PULLING OF TREE STUMPS AND GRADING ACTIVITIES TO DIRECTLY OVER THE TRENCHLINE. DO NOT GRADE OR REMOVE STUMPS OR ROOT SYSTEMS FROM THE REST OF THE RIGHT-OF-WAY IN WETLANDS UNLESS THE CHIEF INSPECTOR AND COMPANY ENVIRONMENTAL INSPECTOR DETERMINE THAT SAFETY RELATED CONSTRUCTION CONSTRAINTS REQUIRE REMOVAL OF TREE STUMPS FROM UNDER THE WORKING SIDE OF THE RIGHT-OF-WAY.
7. TOPSOIL STRIPPING SHALL NOT BE REQUIRED IN SATURATED SOIL CONDITIONS.
8. LEAVE HARD PLUGS AT THE EDGES OF WETLAND UNTIL JUST PRIOR TO TRENCHING.
9. TRENCHING THROUGH WETLANDS MAY PROCEED WHEN THE PIPE SECTION IS FABRICATED AND READY TO LAY. ONCE TRENCHING COMMENCES, CONSTRUCTION THROUGH THE WETLAND IS TO PROCEED CONTINUOUSLY UNTIL THE CROSSING IS COMPLETED, BACKFILLED AND RESTORED IN ORDER TO MINIMIZE THE LENGTH OF THE TRENCH IS OPEN.
10. PIPE SECTION MAY BE FABRICATED WITHIN THE WETLAND ADJACENT TO PIPE TRENCH, OR IN STAGING AREA OUTSIDE THE WETLAND AND WALKED IN. NO CONCRETE COATING ACTIVITY WITHIN 100 FEET OF WETLAND BOUNDARY, UNLESS APPROVED BY COMPANY ENVIRONMENTAL INSPECTOR.
11. LOWER-IN PIPE PRIOR TO BACKFILLING, INSTALL TRENCH PLUGS IN ACCORDANCE WITH DRAWINGS AND SPECIFICATIONS.
12. RESTORE GRADE TO NEAR PRE-CONSTRUCTION TOPOGRAPHY AND INSTALL PERMANENT EROSION CONTROL MEASURES.
13. REMOVE PREFABRICATED MATS FROM WETLANDS UPON COMPLETION.
14. SEED DISTURBED WETLAND AREA (UNLESS STANDING WATER IS PRESENT) AS DETERMINED BY THE ENVIRONMENTAL INSPECTOR AND AS SHOWN ON DRAWINGS AND ECP OR AS APPROVED BY THE APPLICABLE PERMITTING AGENCY.
15. NO FERTILIZER OR LIME IS PERMITTED.
16. DO NOT USE LIQUID MULCH BINDERS WITHIN 100 FT OF WETLANDS OR WATERBODIES.

**TYPE II "SATURATED
WETLAND" INSTALLATION
PROCEDURE**

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

DRAWING NO. SWIP
DATE: 11/11/11
SCALE: 1\"/>



**CROSS SECTION
SCALE: N.T.S.**


**PLAN VIEW
SCALE: N.T.S.**

CONSTRUCTION PROCEDURE NOTES:
1. FLAG WETLAND BOUNDARIES AND INSTALL BOUNDARY SIGNS PRIOR TO CLEARING.
2. NO OVERNIGHT PARKING OR REFUELING OF MOBILE EQUIPMENT IS ALLOWED WITHIN 100 FEET OF WETLAND. PLACE "NO FUELING" SIGN POSTS 100 FEET BACK FROM WETLAND BOUNDARY. REFUEL STATIONARY EQUIPMENT AS PER SPCC PLAN.
3. INSTALL TEMPORARY SLOPE BREAKERS UPSLOPE OF WETLAND BOUNDARIES.
4. INSTALL PREFABRICATED EQUIPMENT MATS THROUGH ENTIRE WETLAND AREA ON THE WORKING SIDE OF THE CONSTRUCTION CORRIDOR.
5. AVOID ADJACENT WETLANDS. INSTALL SEDIMENT BARRIERS AT THE OUTER BOUNDARIES OF THE WETLAND AND ALONG THE DOWN SLOPE EDGE OF THE WETLAND, IF THE DOWN SLOPE OF THE WETLAND IS THE SPILL SIDE WHEN SEDIMENT BARRIERS ARE NOT REQUIRED ON THE WORKING SIDE OF THE CORRIDOR UNLESS EQUIPMENT TRAVELING THROUGH THE WETLAND CAUSES SPILL AND SEDIMENT TO EXIT THE CONSTRUCTION CORRIDOR.
6. LIMIT PULLING OF TREE STUMPS AND GRADING ACTIVITIES TO DIRECTLY OVER THE TRENCHLINE. DO NOT GRADE OR REMOVE STUMPS OR ROOT SYSTEMS FROM THE REST OF THE RIGHT-OF-WAY IN WETLANDS UNLESS THE CHIEF INSPECTOR AND COMPANY ENVIRONMENTAL INSPECTOR DETERMINE THAT SAFETY RELATED CONSTRUCTION CONSTRAINTS REQUIRE REMOVAL OF TREE STUMPS FROM UNDER THE WORKING SIDE OF THE RIGHT-OF-WAY.
7. CONDUCT TRENCHLINE TOPSOIL STRIPPING (IF TOPSOIL IS NOT SATURATED OR FROZEN). SALVAGE TOPSOIL TO ACTUAL DEPTH OR A MAXIMUM DEPTH OF 12 INCHES, AS DETERMINED BY THE ENVIRONMENTAL INSPECTOR. EQUIPMENT MATS MAY BE LOCATED ON SPOIL SIDE, AS REQUIRED.
8. LEAVE HARD PLUGS AT THE EDGES OF WETLAND UNTIL JUST PRIOR TO TRENCHING.
9. TRENCHING THROUGH WETLANDS MAY PROCEED WHEN THE PIPE SECTION IS FABRICATED AND READY TO LAY. ONCE TRENCHING COMMENCES, CONSTRUCTION THROUGH THE WETLAND IS TO PROCEED CONTINUOUSLY UNTIL THE CROSSING IS COMPLETED, BACK FILLED AND RESTORED IN ORDER TO MINIMIZE THE LENGTH OF TIME THE TRENCH IS OPEN.
10. PIPE SECTION MAY BE FABRICATED WITHIN THE WETLAND ADJACENT TO PIPE TRENCH, OR IN STAGING AREA OUTSIDE THE WETLAND AND WALKED IN. NO CONCRETE COATING ACTIVITY SHALL OCCUR WITHIN 100 FEET OF WETLAND BOUNDARY.
11. LOWER-IN PIPE PRIOR TO BACK FILLING TRENCH, INSTALL TRENCH BREAKERS IN ACCORDANCE WITH DRAWINGS AND SPECIFICATIONS.
12. RESTORE GRADE TO NEAR PRE-CONSTRUCTION TOPOGRAPHY, REPLACE TOPSOIL, AND INSTALL PERMANENT EROSION CONTROL MEASURES.
13. REMOVE PREFABRICATED MATS FROM WETLANDS UPON COMPLETION.
14. SEED DISTURBED WETLAND AREAS (UNLESS STANDING WATER IS PRESENT) AS DETERMINED BY THE ENVIRONMENTAL INSPECTOR AND AS SHOWN ON DRAWINGS AND ECP OR AS APPROVED BY THE APPLICABLE PERMITTING AGENCY.
15. NO FERTILIZER OR LIME IS PERMITTED.
16. DO NOT USE LIQUID MULCH BINDERS WITHIN 100 FT OF WETLANDS OR WATERBODIES.

**TYPE I "NON-SATURATED
WETLAND" INSTALLATION
PROCEDURE**

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

DRAWING NO. NWIP
DATE: 11/11/11
SCALE: 1\"/>



CONTRACTOR TO PROVIDE ADEQUATE SUPPORT AT BRIDGE APPROACHES (E.G. CONCRETE BLOCKS, EQUIPMENT MATS) (TYP.)

AREA BETWEEN PIPES SHALL BE MAINTAINED OPEN AND CLEAR OF DEBRIS

NOTES:
1. TIMBER BRIDGES SHALL BE ADEQUATELY ANCHORED AT BOTH ENDS.
2. TEMPORARY STREAM CROSSINGS SHALL BE INSPECTED ON A DAILY BASIS AND BUILD UP OF SEDIMENT OR DEBRIS SHALL BE REMOVED.
3. BRIDGE APPROACHES SHALL BE SUPPORTED WITH EQUIPMENT MATS OR APPROVED EQUAL.
4. SIDE RAILS SHALL BE INSTALLED ON BOTH SIDES OF THE BRIDGE EQUIPMENT CROSSING IN ORDER TO PREVENT SEDIMENT FROM ENTERING THE WATERBODY. SIDE RAILS ARE TO BE CONSTRUCTED OF PLYWOOD NAILED TO THE OUTER EDGES OF THE EQUIPMENT MATS.
5. EQUIPMENT MATS SHALL EXTEND A MINIMUM OF 10 FEET OUTSIDE OF THE WATERBODY OR WETLAND BOUNDARIES.
6. UNLESS OTHERWISE INDICATED ON PLAN, CROSSING SHALL BE REMOVED IMMEDIATELY AFTER CONSTRUCTION IS COMPLETED.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL LOAD CALCULATIONS REQUIRED TO ENSURE THE INSTALLED MATS/EQUIPMENT BRIDGE CAN STRUCTURALLY SUPPORT THE CONSTRUCTION EQUIPMENT TO BE UTILIZED.








**BRIDGE
EQUIPMENT
CROSSING**

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company








DRAWING NO. BEC
DATE: 11/11/11
SCALE: 1\"/>

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
NORTHEAST ENERGY DIRECT PROJECT NEW HAMPSHIRE					
Section:		Township:		Range:	
Co./Par.:		State:		NEW HAMPSHIRE	
Division:		Op. Area:			
Drafter: BZ		Date:		Project ID:	
CHK'd: DL		Date:		Scale:	
Approved: CM		Date:		Filename:	
Sheet: 4 of 13					
Type:					

G:\KinderMorgan\339501_NEDProject\DataProd\Work\Drafting\Standard_Details\NH\CAD\NH_ES_DETAILS_005.dwg — PLOT TIME: 11/14/2015 1:42 AM



NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
<p style="text-align: center;">Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company</p> <p style="text-align: center;">NORTHEAST ENERGY DIRECT PROJECT</p> <p style="text-align: center;">NEW HAMPSHIRE</p>					
Section:		Township:		Range:	
Co./Par.:		State:		NEW HAMPSHIRE	
Division:		Op. Area:			
Drafter: BZ		Date:		Project ID:	
Chk'd: DL		Date:		Filename:	
Approved: CM		Date:			
Sheet: 5 of 13					
Type:					



NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
NORTHEAST ENERGY DIRECT PROJECT NEW HAMPSHIRE					
Section:	Township:	Range:			
Co./Par.:	State:		NEW HAMPSHIRE		
Division:	Op. Area:				
Drafter: BZ	Date:	Project ID:			
CHK'd: DL	Date:	Scale:			
Approved: CM	Date:	Filename:			
					Sheet: 6 of 13
					Type:

NOTES:

- DIVERSION BERM TO BE SLOMO SPEED BUMPS BY CHECKER INDUSTRIAL SAFETY PRODUCTS INC OR APPROVED EQUAL. SPEED BUMPS ARE MANUFACTURED FROM RECYCLED RUBBER COMPOSITE. MODEL NUMBER SB6D-H IS 72" L x 12" W x 2.25" H.
- EACH 72" SECTION OF BERM TO HAVE MOUNTING HOLES SPACED ON 22" MAXIMUM, CENTERS.
- BERM TO DIVERT RUNOFF TO EXISTING SEDIMENT BARRIER.
- WHEN REMOVED, ALL HOLES AND DAMAGE TO EXISTING DRIVEWAY SURFACES SHALL BE REPAIRED.

MATERIAL: COMPRESSED MOLDED RECYCLED RUBBER COMPOSITE

1/2" DIA MOUNTING HOLES TO ACCOMMODATE MOUNTING SPIKES OR LAG BOLTS (4 HOLES TYP.)

TYPICAL RUBBER DIVERSION BERM

DRIVEWAY DIVERSION BERM

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

DRB 43

PLAN VIEW

SECTION A-A

SECTION B-B

NOTES:

- SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE HEIGHT OF THE FILTER.
- IMMEDIATELY UPON STABILIZATION OF EACH CHANNEL, INSTALLER SHALL REMOVE ACCUMULATED SEDIMENT, REMOVE ROCK FILTER, AND STABILIZE DISTURBED AREAS.

ROCK FILTER NO.	LOCATION	D (FT.)	RIPRAP SIZE

THIS TABLE IS INTENTIONALLY LEFT BLANK AND SHOULD BE FILLED IN BY THE PLAN PREPARER.

FOR 3' ≤ D USE R-4
FOR 2' ≤ D < 3' USE R-3
NOT APPLICABLE FOR D < 2'

ROCK FILTER

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

RF 44

OUTLET CROSS-SECTION

UP-SLOPE FACE

NOTES:

- A ROCK FILTER OUTLET SHALL BE INSTALLED WHERE FAILURE OF A SILT FENCE OR STRAW BALE BARRIER HAS OCCURRED DUE TO CONCENTRATED FLOW. ANCHORED COMPOST LAYER SHALL BE USED ON UPSLOPE FACE IN HIGH QUALITY AND EXCEPTIONAL VALUE WATERSHEDS.
- SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET.

ROCK FILTER OUTLET

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

RFO 45

PLAN VIEW

PROFILE VIEW

NOTES:

- THE OUTLET PROTECTION MAY BE DONE USING ROCK RIPRAP, GROUDED RIPRAP, OR GABIONS. RIPRAP SHALL BE COMPOSED OF A WELL-GRADED MIXTURE OF STONE SIZE SO THAT 50 PERCENT OF THE PIECES, BY WEIGHT, SHALL BE LARGER THAN THE D50 SIZE DETERMINED BY USING THE CHART. A WELL-GRADED MIXTURE, AS USED HEREIN, IS DEFINED AS A MIXTURE COMPOSED PRIMARILY OF LARGER STONE SIZES, BUT WITH A SUFFICIENT MIXTURE OF OTHER SIZES TO FILL THE SMALLER VOIDS BETWEEN THE STONES. THE DIAMETER OF THE LARGEST STONE SIZE IN SUCH A MIXTURE SHALL BE 1.5 TIMES THE D50 SIZE.
- THE MINIMUM THICKNESS OF THE RIPRAP LAYER SHALL BE 1.5 TIMES THE MAXIMUM STONE DIAMETER FOR D50 OF 15 INCHES OR LESS; AND 1.2 TIMES THE MAXIMUM STONE SIZE FOR D50 GREATER THAN 15 INCHES.

D 50 (IN)	d max (IN)	MIN. BLANKET THICKNESS (IN)
4	6	9
6	9	14
9	14	20
12	18	27
15	22	32
18	27	32
21	32	38
24	36	43

RIPRAP OUTLET PROTECTION-GENERAL

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

RROP 46

STANDARD CONSTRUCTION DETAIL #22
Super Filter Fabric Fence

NOTES:

- * POSTS SPACED @ 10' MAX. USE 2 1/2" DIA. GALVANIZED OR ALUMINUM POSTS.
- ** CHAIN LINK TO POST FASTENERS SPACED @ 14" MAX. USE NO. 6 GA. ALUMINUM WIRE OR NO. 9 GALVANIZED STEEL PRE-FORMED CLIPS. CHAIN LINK TO TENSION WIRE FASTENERS SPACED @ 60" MAX. USE NO. 10 GA. GALVANIZED STEEL WIRE. FABRIC TO CHAIN FASTENERS SPACED @ 24" MAX. C TO C.

NO. 7 GA. TENSION WIRE INSTALLED HORIZONTALLY AT TOP AND BOTTOM OF CHAIN-LINK FENCE.

FILTER FABRIC FENCE MUST BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8 FEET UPSLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT.

SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE FENCE.

SUPER SILT FENCE-1

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

SSF1 47

AT A MINIMUM THE FABRIC SHALL HAVE THE FOLLOWING PROPERTIES:

FABRIC PROPERTY	MINIMUM ACCEPTABLE VALUE	TEST METHOD
GRAB TENSILE STRENGTH (lb)	120	ASTM D1682
ELONGATION AT FAILURE (%)	20% MAX.	ASTM D1682
MULLEN BURST STRENGTH (lb)	200	ASTM D3786
TRAPEZOIDAL TEAR STRENGTH (lb)	50	
PUNCTURE STRENGTH (lb)	40	ASTM D 751 (MODIFIED)
SLURRY FLOW RATE (gal/min/ft)	0.3	
EQUIVALENT OPENING SIZE	30	US STD. SIEVE CW-02215
ULTRAVIOLET RADIATION STABILITY (%)	80	ASTM G-26

WOODCHIP FILTER BERM

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

SSF2 48

WOODCHIP FILTER BERM

PRIOR TO PLACEMENT OF THE BERM, OBSTRUCTIONS SUCH AS TREE LIMBS, LARGE ROCKS, ETC. SHALL BE REMOVED.

WOOD CHIP FILTER BERM SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BERM SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BERM ALIGNMENT. WOOD CHIP BERMS SHALL NOT BE LOCATED IN AREAS OF CONCENTRATED FLOW OR USED TO CONSTRUCT SEDIMENT TRAPS OR OTHER IMPOUNDMENTS.

A 6" THICK LAYER OF COMPOST SHALL BE ADDED TO THE UPSLOPE SIDE OF ANY WOOD CHIP FILTER BERM LOCATED IN AN HQ WATERSHED. THIS BMP SHALL NOT BE ROUTINELY USED IN EV WATERSHEDS.

BERMS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE HEIGHT OF THE BERM. DAMAGED OR DETERIORATED PORTIONS OF THE BERM SHALL BE REPLACED IMMEDIATELY UPON INSPECTION.

BERMS MAY BE LEVELED WHEN THE TRIBUTARY AREA HAS BEEN PERMANENTLY STABILIZED OR LEFT IN PLACE.

WOODCHIP FILTER BERM

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

WFB 49

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					

Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company

NORTHEAST ENERGY DIRECT PROJECT

NEW HAMPSHIRE

Section:	Township:	Range:
Co./Par.:	State:	NEW HAMPSHIRE
Division:	Op. Area:	
Drafter: BZ	Date:	Project ID:
CHK'd: DL	Date:	Scale:
Approved: CM	Date:	Filename:

Sheet: 7 of 13
Type:

G:\KinderMorgan\339501_NEDProject\Work\Drafting\Standard\Details\E&S_Details\NH\CAD\NH_ES_DETAILS_008.dwg - PLOT TIME: 11/14/2015 12:55 AM

CONSTRUCTION SPECIFICATIONS

- PIT DIMENSIONS ARE OPTIONAL.
- THE STANDPIPE SHOULD BE CONSTRUCTED BY PERFORATING A 12"-24" DIAMETER CORRUGATED OR PVC PIPE.
- A BASE OF 2" AGGREGATE SHOULD BE PLACED IN THE PIT TO A DEPTH OF 12". AFTER INSTALLING THE STANDPIPE, THE PIT SURROUNDING THE STANDPIPE SHOULD BE BACKFILLED WITH 2" AGGREGATE.
- THE STANDPIPE SHOULD EXTEND 12" ABOVE THE LIP OF THE PIT.
- THE OUTLET SHALL BE FILTERED THROUGH AN APPROVED DEWATERING DEVICE TO PREVENT HEAVY SILT LADEN WATER FROM DIRECTLY ENTERING A WATERBODY OR WETLAND.
- THE OUTLET SHOULD BE SITUATED IN A WELL VEGETATED AREA.

WELL POINT/ SUMP PIT

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

OWSP 50

NOTES:

- WATER PUMPED OUT OF TRENCH SHALL NOT BE DISCHARGED DIRECTLY INTO WATERBODIES. WATER SHALL BE DISCHARGED INTO A FILTER BAG OR DEWATERING STRUCTURE.
- PUMP SHALL BE CONTROLLED SO THAT THE DISCHARGE DOES NOT OVERFLOW DEWATERING STRUCTURE. THE DEWATERING STRUCTURE SHALL BE RESIZED IF ADDITIONAL FLOW IS REQUIRED.
- PUMP SUCTION HOSE MUST NOT BE ALLOWED TO COME IN CONTACT WITH TRENCH BOTTOM. PROVISIONS MUST BE MADE TO ELEVATE THE SUCTION HOSE TO AT LEAST ONE FOOT ABOVE THE BOTTOM OF THE PIPE TRENCH UNTIL BOTTOM DEWATERING IS NECESSARY.
- DEWATERING SHALL NOT OCCUR DURING TIMES OF HEAVY RAINFALL EXCEPT AS REQUIRED TO PREVENT FLOODING OF CONSTRUCTION EQUIPMENT LOCATED IN BORE PITS AND TRENCHES.
- PUMPS UTILIZED DURING DEWATERING SHALL BE PLACED WITHIN SECONDARY CONTAINMENT IF POSITIONED WITHIN 100 FEET OF A WETLAND OR WATERBODY.

TRENCH DEWATERING

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

TD 51

STEP 1
ARRANGE HAY BALES OVER GEOTEXTILE FABRIC OR STONE BASE ON LEVEL LAND TIGHTLY PACKED AS SHOWN TO COVER AN AREA APPROXIMATELY 12' x 12'.

STEP 2
INSTALL ANOTHER LAYER OF HAY BALES ON THE OUTER EDGE AS SHOWN.

STEP 3
INSTALL SEDIMENT BARRIER, IF REQUIRED BY THE ENVIRONMENTAL INSPECTOR, AROUND ENTIRE HAY BALE STRUCTURE AS SHOWN.

STEP 4
INSTALL ANOTHER LAYER OF HAY BALES ON THE OUTSIDE OF THE SEDIMENT BARRIER AND SECURE IN PLACE BY DRIVING REBAR OR WOODEN STAKE THROUGH EACH OF THE OUTER HAY BALES. (STAKES NOT SHOWN FOR CLARITY PURPOSES)

NOTES:

- WHERE POSSIBLE, THE STRUCTURE SHALL BE PLACED ON A LEVEL, WELL VEGETATED UPLAND SITE SUCH THAT WATER WILL FLOW AWAY FROM STRUCTURE AND ANY WORK AREAS.
- THE CONTRACTOR SHALL PROPERLY REMOVE AND PROPERLY DISPOSE OF THE DEWATERING STRUCTURE IMMEDIATELY UPON COMPLETION OF DEWATERING OPERATIONS. UNDER NO CIRCUMSTANCES SHALL USED DEWATERING STRUCTURES BE LEFT IN PLACE FOR A PERIOD OF TIME GREATER THAN 48 HOURS AFTER DEWATERING OPERATIONS ARE COMPLETE.
- THE STRUCTURE SHOULD BE POSITIONED SUCH THAT WATER WILL NOT FLOW DIRECTLY INTO ANY WETLANDS OR WATERBODIES.

DEWATERING STRUCTURE

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

DS 52

PLAN VIEW
N.T.S.

SECTION VIEW
N.T.S.

PROFILE VIEW
N.T.S.

PIPE ENERGY DISSIPATER

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

PED 53

DITCH LINE TOPSOIL STRIPPING
N.T.S.

ALSO USED IN NON-SATURATED WETLANDS

DITCH PLUS SPOIL SIDE SEGREGATION
N.T.S.

NOTES:

- ALLOW FOR A 3' SEPARATION BETWEEN THE TOPSOIL PILE AND THE TRENCH SPOIL.
- RETURN TRENCH SPOIL TO TRENCH AND COMPACT. FEATHER OUT EXCESS SPOIL OVER STRIPPED AREA LEAVING A LOW CROWN CENTERED OVER THE TRENCH. ALLEVIATE COMPACTION OF SUBSOILS OVER THE STRIPPED AREA.
- RETURN TOPSOIL EVENLY OVER THE STRIPPED AREA AFTER TRENCH HAS SUFFICIENTLY SETTLED OR HAS BEEN COMPACTED.
- ALLEVIATE COMPACTION OF TOPSOIL OVER ENTIRE RIGHT-OF-WAY.
- SEGREGATED TOPSOIL MAY NOT BE USED FOR PADDING THE PIPE.
- INSTALL SEDIMENT BARRIER AS REQUIRED.

TOPSOIL SEGREGATION-1

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

TS1 54

FULL RIGHT-OF-WAY TOPSOIL STRIPPING - A
N.T.S.

FULL RIGHT-OF-WAY TOPSOIL STRIPPING - B
N.T.S.

NOTES:

- ALLOW FOR A 3' SEPARATION BETWEEN THE TOPSOIL PILE AND THE TRENCH SPOIL.
- RETURN TRENCH SPOIL TO TRENCH AND COMPACT. FEATHER OUT EXCESS SPOIL OVER STRIPPED AREA LEAVING A LOW CROWN CENTERED OVER THE TRENCH. ALLEVIATE COMPACTION OF SUBSOILS OVER THE STRIPPED AREA.
- RETURN TOPSOIL EVENLY OVER THE STRIPPED AREA AFTER TRENCH HAS SUFFICIENTLY SETTLED OR HAS BEEN COMPACTED.
- ALLEVIATE COMPACTION OF TOPSOIL OVER ENTIRE RIGHT-OF-WAY.
- SEGREGATED TOPSOIL MAY NOT BE USED FOR PADDING THE PIPE.
- INSTALL SEDIMENT BARRIER AS REQUIRED.

TOPSOIL SEGREGATION-2

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

TS2 55

FULL RIGHT-OF-WAY TOPSOIL STRIPPING-PARALLELING PIPELINES
N.T.S.

FULL RIGHT-OF-WAY TOPSOIL STRIPPING-SIDE SLOPES
N.T.S.

NOTES:

- ALLOW FOR A 3' SEPARATION BETWEEN THE TOPSOIL PILE AND THE TRENCH SPOIL.
- RETURN TRENCH SPOIL TO TRENCH AND COMPACT. FEATHER OUT EXCESS SPOIL OVER STRIPPED AREA LEAVING A LOW CROWN CENTERED OVER THE TRENCH. ALLEVIATE COMPACTION OF SUBSOILS OVER THE STRIPPED AREA.
- RETURN TOPSOIL EVENLY OVER THE STRIPPED AREA AFTER TRENCH HAS SUFFICIENTLY SETTLED OR HAS BEEN COMPACTED.
- ALLEVIATE COMPACTION OF TOPSOIL OVER ENTIRE RIGHT-OF-WAY.
- SEGREGATED TOPSOIL MAY NOT BE USED FOR PADDING THE PIPE.
- INSTALL SEDIMENT BARRIER AS REQUIRED.


TOPSOIL SEGREGATION-3

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

TS3 56

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
NORTHEAST ENERGY DIRECT PROJECT NEW HAMPSHIRE					
Section:		Township:		Range:	
Co./Par.:		State: NEW_HAMPSHIRE			
Division:		Op. Area:			
Drafted: BZ		Date:		Project ID:	
Chk'd: DL		Date:		Scale:	
Approved: CM		Date:		Filename:	
Sheet: 8 of 13					
Type:					

G:\KinderMorgan\339501_NEDProject\Work\Drafting\Standard\Details\E&S_Details\NH\CAD\NH_ES_DETAILS_009.dwg - PLOT TIME: 11/14/2015 1:10 AM



CONSTRUCTION SPECIFICATIONS


- ALL TEMPORARY SWALES SHALL HAVE UNINTERRUPTED POSITIVE GRADE TO AN OUTLET.
- DIVERTED RUNOFF FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
- DIVERTED RUNOFF FROM AN UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT NON-EROSIVE VELOCITY.
- ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE.
- THE SWALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE, AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPEDE NORMAL FLOW.
- FILLS SHALL BE COMPACTED BY EARTH MOVING EQUIPMENT.
- ALL EARTH REMOVED AND NOT NEEDED FOR CONSTRUCTION SHALL BE PLACED SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE SWALE.
- STABILIZATION SHALL BE AS PER THE FLOW CHANNEL STABILIZATION CHART BELOW:

TYPE OF TREATMENT	GRADE	A(5 AC. OR LESS)	B(5 AC. - 10AC)
1	0.5-3.0%	SEED AND STRAW MULCH	SEED AND STRAW MULCH
2	3.1-5.0%	SEED AND STRAW MULCH	SEED USING JUTE OR EXCELSIOR
3	5.1-8.0%	SEED WITH JUTE OR EXCELSIOR, SOO	RECYCLED CONCRETE EQUIVALENT
4	8.1-20.0%	LINED WITH 4-8" RIP-RAP	ENGINEERED DESIGN
- PERIODIC INSPECTION AND REQUIRED MAINTENANCE MUST BE PROVIDED AFTER EACH RAIN EVENT.

TEMPORARY SWALE

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


TS 57



TYPICAL DRAIN TILE REPAIR ACROSS TRENCH-1

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


DTR1 58



TYPICAL DRAIN TILE REPAIR ACROSS TRENCH-2

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


DTR2 59



ENERGY DISSIPATER

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


ED 60



RIGHT-OF-WAY-CROWNING

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company


ROWC 61



LATERAL INTERCEPT DRAIN

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

LID 62



TRENCH DEWATERING SEDIMENT CORRAL

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

TDSC 63

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					

Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company








NORTHEAST ENERGY DIRECT PROJECT

NEW HAMPSHIRE

Section: _____ Township: _____ Range: _____
Co./Par.: _____ State: NEW HAMPSHIRE
Division: _____ Op. Area: _____
Drafted: BZ Date: _____ Project ID: _____
Chk'd: DL Date: _____ Scale: _____
Approved: CM Date: _____ Filename: _____

Sheet: 9 of 13
Type: _____

G:\KinderMorgan\339501_NEDProject\Drawings\Standard\Drawings\NH_ES_DETAILS_010.dwg - PLOT TIME: 11/14/2015 1:07 AM



NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					








Tennessee Gas Pipeline Company, L.L.C.
a Kinder Morgan company

NORTHEAST ENERGY DIRECT PROJECT

NEW HAMPSHIRE

Section:	Township:	Range:
Co./Par.:	State: NEW HAMPSHIRE	
Division:	Op. Area:	
Drafter: BZ	Date:	Project ID:
Chk'd: DL	Date:	Scale:
Approved: CM	Date:	Filename:
Sheet: 10 of 13		
Type:		

G:\KinderMorgan\339501_NEDProject\Drawings\Standard\Work\Drawings\NH\ES_DETALS_011.dwg - PLOT TIME: 11/14/2015 1:19 AM



NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					


Tennessee Gas Pipeline Company, L.L.C.
 a Kinder Morgan company

NORTHEAST ENERGY DIRECT PROJECT

NEW HAMPSHIRE

Section:	Township:	Range:
Co./Par.:	State: NEW HAMPSHIRE	
Division:	Op. Area:	
Drafter: BZ	Date:	Project ID:
Chk'd: DL	Date:	Scale:
Approved: CM	Date:	Filename:
Sheet: 11 of 13		
Type:		

G:\KinderMorgan\339501_NEDProject\DataProd\Work\Drafting\Standard_Details\E&S_Details\NH\CAD\NH_ES_DETAILS_012.dwg - PLOT TIME: 11/14/2015 1:13 AM



SECTION "A-A" VIEW
SCALE: N.T.S.


NOTES:

- STRUCTURE SHALL BE PLACED ON A LEVEL WELL VEGETATED SITE SUCH THAT WATER WILL FLOW AWAY FROM STRUCTURE AND ANY WORK AREAS AND MINIMIZE EROSION OF THE SURROUNDING AREA TO THE EXTENT PRACTICABLE.
- AT THE DISCRETION OF THE ENVIRONMENTAL INSPECTOR, ADDITIONAL EROSION AND SEDIMENTATION CONTROL DEVICES (E.G. RIPRAP CHECK DAMS, COMPOST FILTER SOCKS, ETC.) MAY BE REQUIRED TO BE INSTALLED DOWNSTREAM OF THE STRUCTURE IF EROSION BECOMES APPARENT DURING DEWATERING.
- FLOW RATES THROUGH DISCHARGE AND DIVERTER PIPES SHALL BE SUCH THAT STRUCTURE WILL NOT OVERFLOW. A MINIMUM FREEBOARD OF 3" MEASURED FROM THE TOP OF THE THIRD ROW OF HAYBALES TO THE WATER SURFACE ELEVATION, SHALL BE MAINTAINED AT ALL TIMES.
- THE 3/4" CRUSHED STONE INSTALLED WITHIN THE BASIN SHALL BE WASHED TO REMOVE ALL DIRT/FINE PARTICLES PRIOR TO INSTALLATION.
- THE CHAINLINK FENCE POSTS SHALL BE DRIVEN A MINIMUM OF 2.5 FT. INTO STABLE, EXISTING GROUND. THE CONTRACTOR MAY BE REQUIRED TO INSTALL THE POLES DEEPER IF STABLE SUBSOILS ARE NOT ACHIEVED WITHIN 2.5 FT.
- AT THE DISCRETION OF THE ENVIRONMENTAL INSPECTOR, ADDITIONAL GEOTEXTILE SEPARATION FABRIC AND 3/4" CRUSHED STONE MAY BE REQUIRED TO BE INSTALLED AROUND THE OUTSIDE EDGE OF THE DEWATERING STRUCTURE.
- CHAINLINK FENCE SHALL INSTALLED TIGHTLY AGAINST THE HAY BALES AND SECURELY FASTENED TOGETHER AT ALL JOINTS WITH CABLE TENSION WIRE AND STRETCHER BARS.
- THE ENVIRONMENTAL INSPECTOR SHALL HAVE THE AUTHORITY TO MODIFY THE DESIGN AS REQUIRED TO PREVENT EROSION AND SEDIMENTATION DOWNSTREAM OF THE STRUCTURE.
- HAY BALES SHALL BE STACKED SUCH THAT THE JOINTS ARE STAGGERED.



HYDROSTATIC DEWATERING STRUCTURE-2

DRAWING NO.	HDS2	DATE	08-2015
SCALE		FIG. NO.	78

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
 Tennessee Gas Pipeline Company, L.L.C. a Kinder Morgan company					
NORTHEAST ENERGY DIRECT PROJECT					
NEW HAMPSHIRE					
Section:		Township:		Range:	
Co./Par.:			State: NEW HAMPSHIRE		
Division:			Op. Area:		
Drafter:	BZ	Date:	Project ID:		
Chk'd:	DL	Date:	Scale:		
Approved:	CM	Date:	Filename:		
					Sheet: 12 of 13
					Type:

G:\KinderMorgan\339501_NEDProject\Work\Detail\NH\ES_Details\NH\CAD\NH_ES_Details_013_LEGEND.dwg - PLOT TIME: 11/14/2015 1:21 AM

NH DETAIL NUMBER	TITLE	ACRONYM
1	SURFACE ROUGHENING	SR
2	STONE OUTLET SEDIMENT TRAP	SOST
3	PIPE OUTLET SEDIMENT TRAP	POST
4	TYPICAL SEDIMENT BASIN	TSB
5	GEOTEXTILE DEWATERING BAG	GDB
6	EROSION BLANKETS SLOPE INSTALLATION	EBSI
7	EROSION BLANKETS CHANNEL INSTALLATION	EBCI
8	TEMPORARY DIVERSION	TD
9	SLOPE DRAIN	SD
10	OVERSIDE DRAIN	OD
11	SILT FENCE INSTALLATION	SF1
12	SILT FENCE TYPICAL PLACEMENT - ONE SLOPE	SF2
13	SILT FENCE TYPICAL PLACEMENT - TWO SLOPES	SF3
14	SILT FENCE PLACEMENT FOR PERIMETER CONTROL	SF4
15	STRAW OR HAY BALE BARRIER	SHBB
16	EROSION CONTROL MIX BERM TYPICAL PLACEMENT - ONE SLOPE	ECB1
17	EROSION CONTROL MIX BERM TYPICAL PLACEMENT - TWO SLOPES	ECB2
18	EROSION CONTROL MIX BERM PLACEMENT FOR PERIMETER CONTROL	ECB3
19	CONTINUOUS CONTAINED BERM	CCB
20	STONE CHECK DAM	SCD
21	CONCRETE BLOCK AND GRAVEL DROP INLET SEDIMENT BARRIER	GCSB
22	GRAVEL & WIRE MESH DROP INLET SEDIMENT BARRIER	GWSB
23	TEMPORARY GRAVEL CONSTRUCTION EXIT	TGCE
24	EARTH OUTLET SEDIMENT TRAP (EXCAVATED)	EST1
25	EARTH OUTLET SEDIMENT TRAP (EMBANKMENT)	EST2
26	TYPE II "SATURATED WETLAND" INSTALLATION PROCEDURE	SWIP
27	TYPE I "NON-SATURATED WETLAND" INSTALLATION PROCEDURE	NWIP
28	BRIDGE EQUIPMENT CROSSING	BEC
29	DAM AND PUMP CROSSING	DPC
30	CULVERT EQUIPMENT CROSSING	CEC
31	TYPICAL MATTING/NETTING INSTALLATION FOR WATER CROSSING	MWCC
32	WETLAND EQUIPMENT CROSSING	WEC
33	BORED ROAD/RAILROAD CROSSING	BRRRC
34	FLUME CROSSING - 1	FC1
35	FLUME CROSSING - 2	FC2
36	DRY WATERBODY CROSSING	DWC
37	TYPICAL OPEN CUT PAVED ROAD CROSSING	OOCR
38	TYPICAL UTILITY LINE CROSSING WITH COFFERDAM	ULCC
39	TEMPORARY ACCESS FORD	TAF
40	TYPICAL TIMBER MAT WATERBODY BRIDGE	TMBW
41	SLOPE BREAKER (WATERBAR)	SB
42	TRENCH BREAKER (TRENCH PLUG)	TB
43	DRIVEWAY DIVERSION BERM	DDB
44	ROCK FILTER	RF
45	ROCK FILTER OUTLET	RFO
46	RIP RAP OUTLET PROTECTION - GENERAL	RROP
47	SUPER SILT FENCE - 1	SSF1
48	SUPER SILT FENCE - 2	SSF2
49	WOODCHIP FILTER BERM	WFB
50	WELL POINT/SUMP PIT	WPSP
51	TRENCH DEWATERING	TD
52	DEWATERING STRUCTURE	DS
53	PIPE ENERGY DISSIPATER	PED
54	TOPSOIL SEGREGATION - 1	TS1
55	TOPSOIL SEGREGATION - 2	TS2
56	TOPSOIL SEGREGATION - 3	TS3
57	TEMPORARY SWALE	TS
58	TYPICAL DRAIN TILE REPAIR ACROSS TRENCH - 1	DTR1
59	TYPICAL DRAIN TILE REPAIR ACROSS TRENCH - 2	DTR2
60	ENERGY DISSIPATER	ED
61	RIGHT OF WAY CROWNING	ROWC
62	LATERAL INTERCEPT DRAIN	LID
63	TRENCH DEWATERING SEDIMENT CORRAL	TDSC
64	WATERBODY CROSSING HORIZONTAL DIRECTION DRILL (HDD)	ARCS
65	TYPICAL ACCESS ROAD CROSS SECTION	WHDD
66	100' CORRIDOR (GREENFIELD) STANDARD	ROW01
67	100' CORRIDOR (GREENFIELD) 50/50	ROW02
68	100 FT. CORRIDOR PIPELINE OUTSIDE POWERLINE EASEMENT FOR 30" PROPOSED PIPELINE	ROW03
69	100 FT. CORRIDOR PIPELINE INSIDE POWERLINE EASEMENT FOR 30" PROPOSED PIPELINE	ROW04
70	95 FT. CORRIDOR PIPELINE OUTSIDE POWERLINE EASEMENT FOR 30" PROPOSED PIPELINE	ROW05
71	TAKE-UP & RELAY FOR SEGMENT P 20" PROPOSED PIPELINE	ROW06
72	75' CORRIDOR PIPELINE OUTSIDE POWERLINE EASEMENT FOR 12" PROPOSED PIPELINE	ROW07
73	75' CORRIDOR (GREENFIELD) FOR PROPOSED 12" PIPELINE	ROW08
74	75' CORRIDOR (WETLANDS) - 1	ROW09
75	75' CORRIDOR (WETLANDS) - 2	ROW10
76	75' CORRIDOR PUSH/PULL WETLAND CROSSING METHOD	ROW11
77	HYDROSTATIC DEWATERING STRUCTURE - 1	HDS1
78	HYDROSTATIC DEWATERING STRUCTURE - 2	HDS2

EROSION AND SEDIMENT CONTROL NOTES:

- EROSION CONTROLS WILL BE INSTALLED IMMEDIATELY FOLLOWING EARTH DISTURBANCE AND WILL BE MAINTAINED UNTIL PERMANENT STABILIZATION. PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATED COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION THROUGHOUT THE SITE.
- ALL WETLAND AND WATERBODY BOUNDARIES WILL BE CLEARLY MARKED/FLAGGED IN THE FIELD PRIOR TO THE COMMENCEMENT OF EARTH DISTURBANCE ACTIVITIES.
- ALL EROSION CONTROL BEST MANAGEMENT PRACTICES (BMPs) MUST BE INSPECTED DAILY IN ACTIVE CONSTRUCTION AREAS AND AT LEAST WEEKLY OR WITHIN ONE DAY FOLLOWING A PRECIPITATION EVENT THAT RESULTS IN STORMWATER RUNOFF IN NON-ACTIVE AREAS. MAINTENANCE, REPAIR OR REPLACEMENT OF FAILING BMPs SHALL BE PERFORMED IMMEDIATELY.
- SUBSOIL EXCAVATED AS PART OF THE PROJECT AND SEDIMENT REMOVED FROM BMPs WILL BE COMBINED AND USED TO BACKFILL THE TRENCH. TYPICALLY, EXCESS SOIL IS MINIMAL AND WILL EITHER BE USED TO CREATE A CROWN OVER THE TRENCH TO COUNTERACT SETTLING OR WILL BE SPREAD EVENLY ACROSS THE ROW, WHICH WILL HAVE A NEGLIGIBLE EFFECT ON THE OVERALL GRADE. ALSO, ANY EXCESS EXCAVATED MATERIALS OR MATERIALS UNSUITABLE FOR BACKFILL WILL BE HANDLED, AS APPROVED BY LANDOWNER OR LAND MANAGEMENT AGENCY, OR DISPOSED OF IN ACCORDANCE WITH APPLICABLE REGULATIONS.
- IT IS ACCEPTABLE FOR E&S BMPs TO BE TEMPORARILY REMOVED FROM EQUIPMENT CROSSING PATHWAYS DURING PERIODS OF ACTIVE CONSTRUCTION IF THESE CONTROLS WILL BE PROPERLY REINSTALLED AT THE END OF EACH WORK DAY.
- WETLAND MATS WILL BE PERMANENTLY REMOVED AFTER CLEAN-UP/RESTORATION.
- MATS WILL BE AT LEAST 12 FEET WIDE AND LENGTH IS DEPENDENT ON THE WETLAND CROSSING LENGTH FROM START TO END.
- WHEN WETLAND AREAS ARE TEMPORARILY DISTURBED, TOPSOIL WILL BE ISOLATED AND STOCKPILED FOR REPLACEMENT AFTER GRADING IS COMPLETED. NO SOIL AMENDMENTS SHOULD BE USED ON WETLAND AREAS.
- TEMPORARY VEGETATIVE COVER SHOULD BE APPLIED WHERE EXPOSED SOIL SURFACES WILL NOT BE FINAL GRADED WITHIN 4 DAYS FROM INITIAL DISTURBANCE. SUCH AREAS INCLUDE EXCAVATED AREAS, SOIL STOCKPILES, BERMS, EMBANKMENTS AND SIDES OF SEDIMENT BASINS, TEMPORARY ROAD BANKS, AND OTHER EARTHWORKS. APPLY TEMPORARY VEGETATION IN ACCORDANCE WITH NEW HAMPSHIRE STORMWATER MANUAL (NHSM) VOLUME 3, CHAPTER 4-1.
- A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES.
- IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE CONTRACTOR SHALL IMPLEMENT APPROPRIATE BMPs TO MINIMIZE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION AND NOTIFY THE NHDES.
- ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BMP, SUCH AS A PUMPED WATER FILTER BAG OR EQUIVALENT SEDIMENT REMOVAL FACILITY, OVER UNDISTURBED VEGETATED AREAS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ANY EXCESS MATERIAL AND MAKE SURE THE SITE(S) RECEIVING THE EXCESS HAS AN APPROVED AND FULLY IMPLEMENTED EROSION AND SEDIMENT CONTROL PLAN THAT MEETS APPLICABLE STATE OR FEDERAL REGULATIONS.
- MAJOR EARTHMOVING ACTIVITIES SHOULD NOT BE CONDUCTED DURING MAJOR RAINSTORMS OR WHEN SPRING THAW IS OCCURRING.
- THE LENGTH OF TIME FOR OPEN TRENCH SHOULD BE MINIMUM TIME NECESSARY TO EFFICIENTLY EXCAVATE THE TRENCH, INSTALL THE PIPE, BACKFILL THE TRENCH, AND BEGIN STABILIZATION OF THE DISTURBED AREAS. THIS TIME PERIODS SHOULD NOT EXCEED 30 DAYS FOR STEEL PIPELINES.
- ADDITIONAL AND/OR MODIFICATIONS TO THE PROPOSED EROSION AND SEDIMENT CONTROLS MAY BE REQUIRED BASED ON PLANS ENCOUNTERED AT THE TIME OF CONSTRUCTION. REVIEWING AGENCY SHALL BE NOTIFIED OF ANY SUBSTANTIVE CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES.
- SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THE PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEEP INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- VEHICLES AND EQUIPMENT SHALL ENTER AND EXIT THE WORKSPACE DIRECTLY ONLY FROM ACCESS POINTS SHOWN ON THE APPROVED E&S PLANS.
- AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES - 6 TO 12 INCHES ON COMPACTED SOILS - PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4-INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING.
- AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY E&S BMPs MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPs AREN'T DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPs MUST BE STABILIZED IMMEDIATELY IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS. SUCH REMOVAL/CONVERSIONS SHOULD BE PERFORMED ONLY DURING THE GERMINATING SEASON.
- ALL CHANNELS SHALL BE KEPT FREE OF OBSTRUCTIONS INCLUDING BUT NOT LIMITED TO FILL, ROCKS, LEAVES, WOODY DEBRIS, ACCUMULATED SEDIMENT, EXCESS VEGETATION, AND CONSTRUCTION MATERIAL/WASTES.
- UNDERGROUND UTILITIES CUTTING THROUGH ANY ACTIVE CHANNEL SHALL BE IMMEDIATELY BACKFILLED AND THE CHANNEL RESTORED TO ITS ORIGINAL CROSS-SECTION AND PROTECTIVE LINING. ANY BASE FLOW WITHIN THE CHANNEL SHALL BE CONVEYED PAST THE WORK AREA IN THE MANNER DESCRIBED IN THIS PLAN UNTIL SUCH RESTORATION IS COMPLETE.
- PLANNING FOR SEEDING AND RESTORATION ACTIVITIES SHALL TAKE PLACE PRIOR TO COMMENCING FINAL RESTORATION ACTIVITIES.
- UPON FINAL COMPLETION OF ANY EARTH DISTURBANCE ACTIVITY OR ANY STAGE OR PHASE OF AN ACTIVITY, THE SITE SHALL IMMEDIATELY HAVE TOPSOIL RESTORED, REPLACED, OR AMENDED, SEEDED, MULCHED OR OTHERWISE PERMANENTLY STABILIZED AND PROTECTED FROM ACCELERATED EROSION AND SEDIMENTATION.
- UPON TEMPORARY CESSATION OF AN EARTH DISTURBANCE ACTIVITY OR ANY STAGE OR PHASE OF AN ACTIVITY WHERE A CESSATION OF EARTH DISTURBANCE ACTIVITIES WILL EXCEED 4 DAYS, THE SITE SHALL BE IMMEDIATELY SEEDED, MULCHED, OR OTHERWISE PROTECTED FROM ACCELERATED EROSION AND SEDIMENTATION PENDING FUTURE EARTH DISTURBANCE ACTIVITIES.
- TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN DRAWINGS IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. TOPSOIL STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SIDE SLOPES MUST BE 2:1 OR FLATTER.
- TOPSOIL SHOULD NOT BE PLACED WHILE THE TOPSOIL OR SUBSOIL IS IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBSOIL IS EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED PREPARATION. COMPACTED SOILS SHOULD BE SCARIFIED 6 TO 12 INCHES ALONG CONTOUR WHENEVER POSSIBLE PRIOR TO SEEDING.

(CONT)

- IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE OPERATOR SHALL STABILIZE THE DISTURBED AREAS. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE RE-DISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINAL GRADE OR WHICH WILL NOT BE RE-DISTURBED WITHIN 1 YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS.
- AN EROSION CONTROL BLANKET SHALL BE APPLIED AT THE BASE OF GRASSED WATERWAYS, ON STEEP SLOPES (> 15%), AND ON ANY DISTURBED SOIL WITHIN 100 FEET OF LAKES, STREAMS, AND WETLANDS.
- IRREGULARITIES IN THE SOIL SURFACE SHALL BE CORRECTED TO PREVENT THE FORMATION OF DEPRESSIONS.

PROJECT SEQUENCE AND SCHEDULE:

GENERAL CONDITIONS:

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED AND IMMEDIATELY STABILIZED BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING, GRUBBING AND TOPSOIL STRIPPING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE. ANY DEVIATION FROM THE FOLLOWING SEQUENCE MUST BE APPROVED IN WRITING FROM THE NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES (NHDES).

CONSTRUCTION WILL TAKE PLACE IN A SINGLE SPREAD. PIPELINE CONSTRUCTION CREWS WILL BE IN CLOSE PROXIMITY TO EACH OTHER AND WILL BE ABLE TO EFFICIENTLY COMMUNICATE DURING THE ENTIRE CONSTRUCTION PHASE OF THE PROJECT. THE MINIMAL LENGTH OF EACH CONSTRUCTION SPREAD WILL NOT REQUIRE CONSTRUCTION CREWS TO BE SEPARATED BY SIGNIFICANT DISTANCES DURING PIPELINE CONSTRUCTION.

WORK EFFORT WILL BE SUBDIVIDED INTO CATEGORIES AND PERFORMED BY SPECIALIZED CREWS (E.G. SITE PREPARATION/CLEARING, TRENCHING, PIPE CONSTRUCTION, ETC). EACH CREW WILL PROGRESS IN A LOGICAL MANNER, GENERALLY FROM THE BEGINNING TO THE END OF THE PIPELINE. THE TIME PERIOD BETWEEN TRENCH EXCAVATION AND FINAL STABILIZATION SHALL BE MINIMIZED TO THE EXTENT PRACTICABLE. NO ONE SEGMENT OF AREA OF THE PIPELINE ALIGNMENT SHALL GO WITHOUT STABILIZATION (TEMPORARY OR PERMANENT) FOR A PERIOD GREATER THAN FOUR DAYS. THE FOLLOWING DESCRIBES THE TYPICAL SEQUENCE OF CONSTRUCTION ACTIVITIES THAT SHALL OCCUR WITHIN THE TYPES OF AREAS DESCRIBED BELOW, WHICH WILL BE ENCOUNTERED DURING CONSTRUCTION.

- CONSTRUCTION PREPARATION ACTIVITIES**
 - AT LEAST 7 DAYS PRIOR TO INITIATING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING, GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, ALL APPLICABLE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION, AND A REPRESENTATIVE OF THE NHDES TO AN ON-SITE PRE-CONSTRUCTION MEETING.
 - AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY DIG SAFE FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
 - ESTABLISH CONSTRUCTION SUPPORT FACILITIES.
 - IDENTIFY UTILITIES AND OTHER CRITICAL SITE FEATURES TO BE PROTECTED.
 - FLAG AND/OR STAKE WETLAND AND OTHER SENSITIVE AREAS TO BE PROTECTED.
 - FLAG AND/OR STAKE PROPOSED CONSTRUCTION LIMITS OF DISTURBANCE.
 - INSTALL TEMPORARY GRAVEL CONSTRUCTION EXITS.
 - INSTALL ACCESS ROAD.
 - BRUSH HOG/MOW EXISTING VEGETATION TO FACILITATE INSTALLATION OF TEMPORARY EROSION AND SEDIMENT CONTROL.
 - INSTALL TEMPORARY VEHICULAR STREAM CROSSING (E.G., BRIDGE OR MULTIPLE PIPE CROSSING) AND TIMBER MAT WETLAND CROSSING.
 - INSTALL TEMPORARY EROSION AND SEDIMENT CONTROL IN ACCORDANCE WITH THIS PLAN. EROSION AND SEDIMENT CONTROL INSTALLATION, SIMILAR TO OTHER ACTIVITIES, MAY BE CONDUCTED AS PLANS ENCOUNTERED AT THE TIME OF CONSTRUCTION. SOIL DISTURBANCE SHALL BE MINIMIZED UNTIL THE APPROPRIATE TEMPORARY EROSION AND SEDIMENT CONTROLS HAVE BEEN INSTALLED IN THE PROPOSED WORK AREA.
- SITE CLEARING (TREE CUTTING) & GRUBBING**
 - INITIATE CLEARING AND GRUBBING OF RIGHT-OF-WAY AND ACCESS ROADS AS NEEDED.
 - WOODY VEGETATION CLEARING OF THE ROW, ATMS AND STAGING AREAS WILL TAKE PLACE IN A SINGLE PASS. NO GRADING OR GRUBBING WILL OCCUR DURING CLEARING OPERATIONS.
 - HAUL MERCHANTABLE TIMBER OFF-SITE OR STACK AT A DESIGNATED LOCATION, AS DETERMINED BY LANDOWNER SPECIAL CONDITIONS OR ENVIRONMENTAL INSPECTOR.
 - CHIP UNMERCHANTABLE MATERIALS AND SPREAD EVENLY WITHIN THE RIGHT-OF-WAY LIMITS, EXCEPT IN WETLANDS, AGRICULTURE FIELDS, AND MANICURED LAWNS.
 - GRUB TREE STUMPS IN CLEARED ROW. GRIND STUMPS AND REMOVE FROM ROW AND HAUL OFF SITE OR STOCKPILE AT STAGING AREAS FOR USE AS MULCH STABILIZATION AFTER EARLY DISTURBING ACTIVITIES ARE COMPLETED.
 - NOTIFY THE NHDES AFTER INSTALLATION OR STABILIZATION OR ALL PERIMETER SEDIMENT CONTROL BMPs (INCLUDING TOPSOIL PILES) WITHIN A NEW WORK AREA AND AT LEAST 3 DAYS PRIOR TO PROCEEDING WITH BULK EARTH DISTURBANCE ACTIVITIES.
- SITE GRADING AND STABILIZATION**
 - RE-STAKE THE ROW TO REPLACE ANY SIGNAGE OR FLAGGING THAT WAS REMOVED OR DAMAGED DURING CLEARING ACTIVITIES.
 - INSTALL TEMPORARY GRAVEL CONSTRUCTION EXITS WHERE VEHICLES WILL EXIT CONSTRUCTION AREAS FROM ACCESS ROADS.
 - CLEAR, GRADE AND IMPROVE ACCESS ROAD AS NEEDED AS THEIR USE BECOMES REQUIRED.
 - STOCKPILE TOPSOIL ALONG THE EDGE OF THE RIGHT-OF-WAY WHERE INDICATED AND TEMPORARILY STABILIZED.
 - ROUGH GRADE SITE, REMOVE AND STOCKPILE TOPSOIL AS APPROPRIATE. INSTALL SILT FENCE AS SHOWN ON E&S DRAWINGS.
 - THE MIXING OF TOPSOIL WITH SUBSOIL SHALL BE PREVENTED BY STRIPPING TOPSOIL FROM THE WORK AREA WITHIN DESIGNATED AREAS AND IN COORDINATION WITH THE APPLICABLE ACCESS AGREEMENTS.
 - INSTALL TEMPORARY SLOPE BREAKERS AS SHOWN ON E&S DRAWINGS.
 - INSTALL TEMPORARY FLOW DIVERSION, FLUME STRUCTURES AND TEMPORARY BRIDGES AT STREAM CROSSINGS AS STREAM CROSSINGS ARE ENCOUNTERED.
 - INSTALL APPROPRIATE TRENCH DEWATERING AND FILTERS SURROUNDING SEDIMENT BARRIERS (STRAW BALES, SILT FENCE AND/OR COMPOST FILTER SOCKS AS DETERMINED IN THE FIELD) IN PREPARATION OF DEWATERING ACTIVITIES. THIS SHALL BE COMPLETED PRIOR TO PERFORMING EXCAVATION ACROSS WATERBODIES.
 - INSTALL TIMBER MATS FOR EQUIPMENT ACCESS AS SHOWN ON E&S DRAWINGS AS WETLANDS/STREAMS ARE ENCOUNTERED.
 - UTILIZED WOOD CHIPS IN HEAVILY TRAFFICKED AREAS TO REDUCE THE POTENTIAL FOR RUTTING EXCEPT IN WETLANDS.
- PIPELINE CONSTRUCTION**

UPLAND LOCATIONS:

 - ENSURE THE APPROPRIATE UPLAND EROSION AND SEDIMENT CONTROLS ARE IN PLACE.
 - GRADE/EXCAVATE PIPELINE TRENCH AND RIGHT-OF-WAY.
 - SEGREGATE TOPSOIL IN AGRICULTURAL FIELDS AND MANICURED LAWNS FOR RESTORATION ACTIVITIES DURING FINAL CLEAN UP.
 - STRING PIPE AND PREPARE THE PIPE JOINTS FOR WELDING.
 - WELD PIPE JOINTS AND PERFORM NDT (NON-DESTRUCTIVE TESTING).
 - DISCHARGE ALL WATER FROM TRENCH USING FILTER BAGS OR COMPOST SOCK SEDIMENT TRAP.
 - INSTALL THE PIPELINE IN THE TRENCH.
 - INSTALL TRENCH PLAGS.
 - BACKFILL THE PIPELINE TRENCH.
 - PERFORM PERMANENT STABILIZATION, INCLUDING:
 - GRADE AREAS AS CLOSELY AS POSSIBLE TO ORIGINAL CONTOURS.
 - REPLACE TOPSOIL.
 - APPLY PERMANENT SEEDING, SOIL AMENDMENTS AND MULCH OR EROSION CONTROL BLANKETS.

(CONT)

ROADWAY, DRIVEWAYS AND RAILROADS CROSSINGS:

- STRING PIPE OUTSIDE OF ROAD/DRIVEWAY AND PREPARE THE PIPE JOINTS FOR WELDING AND NON-DESTRUCTIVE TESTING.
- EXCAVATE PIPELINE TRENCH FOR THE OPEN TRENCH CROSSING OR EXCAVATE BORE PITS FOR CONVENTIONAL BORED CROSSING.
- DISCHARGE ALL WATER FROM TRENCH.
- MOVE THE PIPE SECTIONS TO THE TRENCH OR PERFORM CONVENTIONAL BORE.
- INSTALL THE PIPELINE IN THE TRENCH.
- INSTALL TRENCH PLAGS AS SHOWN ON E&S DRAWINGS.
- BACKFILL THE PIPELINE TRENCH.


STREAM CROSSING (LESS THAN 24 HOURS FOR STREAM LESS THAN 10 FEET WIDE, LESS THAN 48 HOURS FOR STREAMS BETWEEN 10 AND 100 FEET WIDE):

- ADJUST EROSION AND SEDIMENT CONTROLS AS NEEDED TO PERFORM WORK AT STREAM CROSSING LOCATIONS.
- INSTALL SANDBAG DIVERSION DAM OR OTHER NHDES-APPROVED DAM AROUND CHANNEL WORKAREA.
- ALL NON-PERENNIAL STREAMS AND DITCHES WILL BE FLUMED ONLY IF WATER IS PRESENT.
- DEWATER OPEN-CUT TRENCH WORK AREA WITH THE STREAM USING FILTER BAG OR COMPOST SOCK SEDIMENT TRAP AS NEEDED.
- EXCAVATE PIPELINE TRENCH.
- TEMPORARY TOPSOIL AND SUBSOIL STOCKPILES SHALL BE LOCATED AT LEAST 10 FEET AWAY FROM TOP OF STREAM BANKS.
- IN AN UPLAND LOCATION, STRING PIPE AND PREPARE THE PIPE JOINTS FOR WELDING AND NON-DESTRUCTIVE TESTING.
- DISCHARGE ALL WATER FROM TRENCH USING FILTER BAGS OR COMPOST SOCK
- INSTALL THE PIPELINE IN THE TRENCH.
- INSTALL TRENCH PLAGS AT TOP OF STREAM BANKS.
- BACKFILL THE PIPELINE TRENCH.
- PERFORM PERMANENT STABILIZATION, INCLUDING:
 - GRADE AREAS AS CLOSELY AS POSSIBLE TO ORIGINAL CONTOURS.
 - REPLACE TOPSOIL.
 - APPLY PERMANENT SEEDING, SOIL AMENDMENTS AND EROSION CONTROL BLANKET.
- REMOVE TEMPORARY CONTROL MEASURES.

WETLAND CROSSING:

- ADJUST EROSION AND SEDIMENT CONTROLS AS NEEDED TO WORK IN STREAM CROSSING LOCATIONS.
- EXCAVATE THE TOP 1-FOOT OF TOPSOIL AND STOCKPILE SEPARATELY FROM THE SUBSOIL.
- IN AN UPLAND LOCATION, STRING PIPE AND PREPARE THE PIPE JOINTS FOR WELDING AND NON-DESTRUCTIVE TESTING.
- DISCHARGE ALL WATER FROM TRENCH USING FILTER BAGS OR COMPOST SOCK SEDIMENT TRAP.
- INSTALL THE PIPELINE IN THE TRENCH.
- INSTALL TRENCH PLAGS AT EDGE OF WETLAND.
- BACKFILL THE PIPELINE TRENCH.
- PERFORM PERMANENT STABILIZATION, INCLUDING:
 - REPLACE SUBSOIL MATERIAL.
 - REPLACE TOPSOIL SUCH THAT THERE IS NO CROWNING OF SOIL MATERIAL.
 - APPLY TEMPORARY SEEDING.

- DEMOLITION AND SITE CLEAN UP**
 - COMPLETE PERMANENT STABILIZATION OF ALL REMAINING AREAS OF DISTURBANCE, INCLUDING:
 - GRADE AREAS AS CLOSELY AS POSSIBLE TO ORIGINAL CONTOURS.
 - REPLACE TOPSOIL.
 - APPLY PERMANENT SEEDING, SOIL AMENDMENT, AND MULCH OR EROSION CONTROL BLANKET.
 - UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER/OR OPERATOR SHALL CONTACT THE NHDES FOR AN INSPECTION PRIOR TO THE REMOVAL/CONVERSION OF THE EROSION AND SEDIMENT CONTROL BMPs
 - REMOVE TEMPORARY CONTROL MEASURES UPON APPROVAL OF THE NHDES.
 - UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES, REMOVAL OF ALL TEMPORARY BMPs, INSTALLATIONS OF ALL PERMANENT BMPs, AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE NHDES FOR A FINAL INSPECTION.
 - ANY MATERIALS NOT INCORPORATED AS TRENCH BACKFILL OR GENERAL GRADING (E.G. UNCONTAMINATED SOIL, ROCK, STONE, GRAVEL, BRICK AND BLOCK, CONCRETE AND USED ASPHALT) AND WASTE FROM LAND CLEARING, GRUBBING AND EXCAVATION, INCLUDING TREES, BRUSH, STUMPS AND VEGETATIVE MATERIAL) WILL BE REUSED, RECYCLED OR REMOVED FROM THE CONSTRUCTION WORK LIMITS IN ACCORDANCE WITH GENERAL EROSION AND SEDIMENT CONTROL NOTES.
 - CONTRACTOR DEMOBILIZATION.
- POST-CONSTRUCTION**
 - CONTINUE TO CONDUCT INSPECTIONS UNTIL THE SITE HAS REACHED PERMANENT STABILIZATION.
 - PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
 - TEMPORARY E&S BMPs MAY BE REMOVED AFTER THE ENTIRE CONTRIBUTORY AREA TO EACH BMP REACHES PERMANENT STABILIZATION.
 - REMOVE ANY REMAINING TEMPORARY WATERBODY AND WETLAND EQUIPMENT CROSSINGS.
 - REMOVE ANY REMAINING TEMPORARY GRAVEL CONSTRUCTION EXITS.
 - PRIOR TO APPLICATION OF THE SEED IN ALL SUPPORT & STAGING AREAS, THE SEEDBED WILL BE PREPARED TO A DEPTH OF 3 TO 4 INCHES USING APPROPRIATE EQUIPMENT TO PROVIDE A FIRM, SMOOTH SEEDBED THAT IS FREE OF DEBRIS AND SCARIFIED TO ENSURE SEEDS LODGE AND GERMINATE.

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
REVISIONS					
					
NORTHEAST ENERGY DIRECT PROJECT LEGEND NEW HAMPSHIRE					
Section:		Township:		Range:	
Co./Par.:		State:		NEW_HAMPSHIRE	
Division:		Op. Area:			
Drawer:	HMM	Date:	Project ID:		
Chk'd:	DL	Date:	Scale:		
Approved:	CM	Date:	Filename:		
					Sheet: 13 of 13
					Type: